

- 1. VALVE JUMPER METER SHALL BE INSTALLED INSIDE VALVE VAULT AND MUST BE VISIBLE FROM THE GROUND SURFACE. INSTALLATION OUTSIDE OF THE VALVE VAULT MUST BE APPROVED BY THE ENGINEER.
- VALVE JUMPER METER SHALL BE PROTECTED FROM COLD WEATHER WITH BLANKETS WHEN NECESSARY.
- 3. JUMPER SHALL BE INSTALLED IMMEDIATELY AFTER SECOND DAY CHLORINATION SAMPLE (SEE UW-09A).
- 4. ALL FITTINGS, WHIPS, AND HARDWARE NECESSARY TO CONNECT 1" CORPORATION STOPS TO CERTIFIED VALVE JUMPERS ARE THE RESPONSIBILITY OF THE CONTRACTOR.

Revised Drawing Name Drawing Number 1. 06/12/2015 UW-05 WATER VALVE 2. 8/18/2023 JRG JUMPER INSIDE VALVE VAULT. 1" CORP JUMPER Date: 06/01/2015 City of Drawn Checked Crystal Lake VR JH