

WATERMAIN TESTING AND CHLORINATION PROCEDURE

UW-09A

STANDARD SPECIFICATIONS FOR WATER AND SEWER CONSTRUCTION IN ILLINOIS (LATEST EDITION) AND AWWA STANDARD C600-17 SHALL APPLY ALONG WITH THE FOLLOWING:

2 HOUR PRESSURE AND LEAKAGE TEST

1. PRETEST: THE CONTRACTOR SHALL PROVIDE A MAP OF THE FACILITIES (WATER MAINS, HYDRANTS, VALVES, ETC.) TO BE INCLUDED DURING THE TEST TO THE ENGINEER. SEE UW-09B WORKSHEET. ALL FIRE HYDRANT AUXILIARY VALVES SHALL BE OPENED SO TESTING IS PERFORMED AGAINST FIRE HYDRANTS. THE ENGINEER WILL COORDINATE WITH THE WATER DEPARTMENT TO SCHEDULE OPENING OF CITY VALVES AND FILLING OF NEW WATER MAIN A MINIMUM OF 48 HOURS IN ADVANCE OF THE TEST. THE CONTRACTOR SHALL NOT OPERATE ANY VALVES ON EXISTING CITY WATER MAIN WITHOUT WRITTEN PERMISSION.
2. HYDROSTATIC PRESSURE TESTING: ALL TESTING EQUIPMENT AND LABOR NECESSARY TO SETUP AND RUN THE TEST SHALL BE PROVIDED BY THE CONTRACTOR AND SHALL INCLUDE:
 - A) PRESSURE GAUGE LOCATED AT HIGHEST POINT OF ELEVATION OF THE WATER MAIN
 - B) PUMP
 - C) TANK
 - D) FITTINGS FOR TESTING EQUIPMENT TO BE CONNECTED TO WATER MAIN
 - E) ACCURATE WATER VOLUME MEASURING DEVICE (CALIBRATED VOLUMETRIC METER OR 1 GALLON GRADUATED CYLINDER IN OUNCES)
3. AIR REMOVAL: AFTER FILLING THE WATERMAIN, AIR SHALL BE EXPELLED BY FLUSHING WATER OUT OF THE MAIN AT FIRE HYDRANTS OR CORPORATION STOPS LOCATED AT HIGH POINTS ALONG THE WATER MAIN.
4. PRESSURIZATION: AFTER ALL AIR HAS BEEN REMOVED, THE MAIN SHOULD BE PRESSURIZED TO MINIMUM 150 PSI BY PUMPING ADDITIONAL WATER INTO THE WATER MAIN.
5. TWO HOUR TEST: ONCE TESTING PRESSURE IS OBTAINED, THE PUMP SHOULD BE SHUT OFF AND TIMING STARTED. THE PRESSURE GAUGE SHOULD BE CHECKED INTERMITTENTLY AND THE PRESSURE READING RECORDED AFTER TWO HOURS. IF THE PRESSURE READING VARIES MORE THAN +/- 5 PSI FROM THE INITIAL PRESSURE, THE TEST FAILS. THE LEAK SHALL BE FOUND AND ADDRESSED PRIOR TO RETESTING.
6. MAKE UP VOLUME: IF THE PRESSURE IS MAINTAINED WITHIN +/- 5 PSI FOR THE TWO HOUR TEST, THE MAKE-UP VOLUME SHALL BE DETERMINED BY PUMPING WATER BACK INTO THE WATER MAIN TO REACH THE INITIAL TEST PRESSURE. THIS WILL NORMALLY BE DONE BY EXCEEDING THE TEST PRESSURE, AND USING THE BLEED OFF VALVE TO DROP THE PRESSURE TO THE INITIAL TEST PRESSURE. ONCE THE INITIAL TEST PRESSURE HAS BEEN REACHED, THE BLEED OFF VALVE SHALL BE OPENED AND WATER THAT LEAVES THE SYSTEM SHALL BE COLLECTED IN THE VOLUME MEASURING DEVICE. ONCE THE GAUGE REACHES THE FINAL TWO HOUR TEST PRESSURE, THE VOLUME OF WATER COLLECTED SHALL BE MEASURED.
7. ALLOWABLE MAKE-UP VOLUME: THE MEASURED VOLUME OF "MAKE UP" WATER SHALL BE COMPARED TO THE ALLOWABLE LEAKAGE. THE ALLOWABLE LEAKAGE SHALL BE CALCULATED BY THE ENGINEER USING THE FORMULA ABOVE. IF THE WATER COLLECTED IS LESS THAN THE ALLOWABLE MAKE UP VOLUME, THE TEST PASSES. IF THE WATER COLLECTED IS MORE THAN THE ALLOWABLE MAKE UP VOLUME, THE TEST FAILS. THE LEAK SHALL BE FOUND AND ADDRESSED PRIOR TO RETESTING.
8. FINAL VALVE CHECK: PRIOR TO BLEEDING OFF THE PRESSURE, ALL HYDRANTS ON THE TESTING MAP SHALL BE SLOWLY OPENED TO ENSURE THAT THEY HAD PRESSURE AGAINST THEM DURING TESTING. THE PRESSURE GAUGE SHOULD DROP AS THE HYDRANTS ARE OPENED ENSURING THAT ALL VALVES IN THE SYSTEM WERE PROPERLY OPENED/CLOSED DURING TESTING.
9. IF THE WATER MAIN HAS PASSED THE PRESSURE TEST, THE PRESSURE SHALL BE REDUCED TO THE CITY'S SYSTEM PRESSURE.

CHLORINATION

1. PRE-CHLORINATION: THE ENGINEER WILL COORDINATE WITH THE WATER DEPARTMENT TO SCHEDULE OPENING OF CITY VALVES FOR CHLORINATION A MINIMUM OF 48 HOURS IN ADVANCE OF THE CHLORINATION. THE FOLLOWING METHODS OF CHLORINE APPLICATION ARE APPROVED BY THE CITY
 - A) LIQUID CHLORINE WITH CHLORINATION DEVICE AND BACKFLOW PREVENTER
 - B) CHLORINE BEARING COMPOUNDS IN WATER
 - C) TABLET DISINFECTION
2. SAMPLING LOCATIONS: THE ENGINEER SHALL DETERMINE THE LOCATION AND QUANTITY OF SAMPLING LOCATIONS. MAXIMUM SPACING BETWEEN SAMPLES SHALL BE 1,200 FEET. THE CHLORINE SOURCE AND ALL DEAD ENDS SHALL BE SAMPLED. SEE UW-09B WORKSHEET.
3. CHLORINATION: THE INITIAL CHLORINE CONCENTRATION SHALL BE 50 mg/L WITH A MINIMUM 24 HOUR RESIDUAL OF 25 mg/L. ALL NEW VALVES AND HYDRANTS SHALL BE OPERATED WHILE THE LINE IS BEING CHLORINATED. THE FINAL FLUSHING RESIDUAL IN THE NEW CHLORINATED LINES SHALL BE BETWEEN 0.2-2.0 mg/L.
4. TESTING: ALL WATER SAMPLES SHALL BE COLLECTED ON TWO CONSECUTIVE DAYS AND PASS BACTERIOLOGICAL TEST RESULTS FROM A CERTIFIED LABORATORY. TEST RESULTS SHALL BE EMAILED TO THE CITY OF CRYSTAL LAKE SO THE IEPA PERMIT APPLICATION CAN BE SUBMITTED. IN THE EVENT THAT THE FIRST SET OF SAMPLES TAKEN TWO CONSECUTIVE DAYS APART FAIL TO PASS, ANOTHER SET OF SAMPLES ME BE TAKEN TWO DAYS APART. IF THE SECONDS SET FAILS TO PASS TESTING, THE PROCEDURE MUST BE REPEATED WITH THE WATER MAIN BEING RECHLORINATED, REFLUSHED AND RESAMPLED.
5. MAINTAIN PRESSURE: IMMEDIATELY AFTER THE SECOND DAY SAMPLE HAS BEEN TAKEN, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO INSTALL A CERTIFIED WATER VALVE JUMPER (SEE UW-05) TO MAINTAIN PRESSURE ON THE NEW WATER MAIN UNTIL THE IEPA PERMIT IS RECEIVED. AFTER RECEIVING THE IEPA OPERATING PERMIT, THE CITY OF CRYSTAL LAKE SHALL OPEN THE VALVE BETWEEN THE NEW AND EXISTING WATERMAIN AND THE WATER VALVE JUMPER MAY BE REMOVED. WATER VALVE JUMPERS ARE AVAILABLE FOR RENT AT THE CITY OF CRYSTAL LAKE WATER DEPARTMENT. IF WATER IN EXCESS OF THE ALLOWABLE LEAKAGE ENTERS THE NEW WATER MAIN THROUGH THE WATER VALVE JUMPER ,THE CONTRACTOR SHALL LOCATE THE LEAK. IF THE NEW WATER MAIN MUST BE DEPRESSURIZED TO FIX A LEAK, THE SYSTEM SHALL BE RETESTED, RECHLORINATED, REFLUSHED, AND RESAMPLED.

Revised:
1. 06/12/2015
2. 8/18/2023 - JRG Leakage formula, procedure, delete 24 hour test
3.
4.

Drawing Name

**WATER MAIN PRESSURE
TEST AND CHLORINATION
PROCEDURE**

Drawing Number
UW-09A
Date: 09/20/2012
Drawn Checked
DD VR

