TOPSOIL STOCKPILING:

- Location of any on-site topsoil stockpiles shall be identified on the approved plans with silt fence installed around the perimeter of the stockpile.
- Topsoil stockpiled for future use shall be relatively free from large roots, sticks, weeds, brush, stones larger than one (1) inch diameter, or other litter and waste products including other extraneous materials not conducive to plant growth.
- Topsoil shall be stockpiled in sequence to eliminate any re-handling or double movements by the Contractor. Failure to properly sequence the stockpiling operations shall not constitute a claim for additional compensation. No material shall be stockpiled in front yards, in utility easements, or in the right-of-way lines.
- 4. If a stockpile is to remain in place for more than (14) calendar days, it is required that the stockpile meet the requirements as outlined in section 595 of the City Code.

UNDERGROUND UTILITY:

- 1. The Contractor shall coordinate water main, water service, sanitary and storm sewer inspections and testing with the Community Development at least 24 hours in advance.
- All main line sanitary shall be cleaned and televised (provide DVD to the City's Engineering Division).
- 3. All manhole or valve covers shall be imprinted "City of Crystal Lake Sanitary", or "City of Crystal Lake Storm", or "City of Crystal Lake Water" as directed by the City.
- Reference the latest edition of the Standard Specifications for Water and Sewer Main Construction in Illinois.
- 5. Existing manholes to be circular cored and booted.

EROSION CONTROL:

- All specified erosion control measures shall be installed and maintained per the requirements of the Crystal Lake Stormwater Ordinance in accordance with the active NPDES permit.
- 2. All slopes 4:1 or steeper shall be sodded or blanketed immediately after mass earthwork.
- 3. All overland flow routes to be stabilized by sod or blanket.
- Erosion control measures to be inspected and approved by City Engineering Division prior to additional work on site.
- Continuous monitoring of erosion control measures is required. Maintain records of weekly reports per the City of Crystal Lake Stormwater Ordinance.
- The Contractor shall implement any additional erosion control measures deemed necessary by the City per the standards of the City Of Crystal Lake Stormwater Ordinance.
- 7. All storm sewer catch basins, sumps and/or retention basins provided are to be cleaned at the end of construction of the project prior to final acceptance. Cleaning may also be required during the course of the construction of the project if it is determined that the silt and debris traps are not properly functioning and their performance is impaired.
- 8. Rip-rap material RR 2 (6") RR4 (16") shall be in accordance with Article 281
- Projects of 1 Acre or greater must obtain an NPDES permit prior to commencement of any construction activity.

Rev	!!	
KOV	חשפו	•
1100	IUUU	

1. 06/12/2015

2. 02/25/2020

3.

4

Drawing Name

STANDARD NOTES AND SPECIFICATIONS

Drawing Number

GE-02b

Date: 01/30/15

Drawn Checked DD AW

